NJTPA - Local Concept Development Study Monmouth County Bridge S-32 on Rumson Road (CR 520) over the Shrewsbury River

Public Information Center



February 27, 2012



- Rumson-Sea Bright Bridge S-32 was built in 1952.
- Routine maintenance can no longer address deficiencies.
- Bridge is in need of major rehabilitation or replacement.
- NJTPA/Monmouth County Local Concept Development (LCD) Study initiated October 2011.
- New program provides opportunity to advance this project with public input and agency collaboration.




Local Concept Development Process

Local Concept Development	Local Preliminary Engineering	Final Design/ Right of Way Acquisition	Construction
Purpose and Need Statement	Approved Design Exception Report	Construction Contract Documents and PS&E package	Completed Construction
Date Collection and Environmental Screening Report	Cost Estimates (Final Design, ROW and Construction)	Environmental Reevaluations	As-Built
Selection of Preliminary Preferred Alternative	Approved Environmental Document	Environmental Permits	Update and Finalize Design Communications Report
NEPA Classification	Approved Project Plan	Acquisition on ROW	Close-out Documentation
Concept Development Report	Preliminary Engineering Report	Update Design Communications Report	
Create Design Communications Report	Update Design Communications Report		



Local Concept Development Process



- Federally funded project requires NEPA (National Environmental Protection Act) documentation
- Identify environmental resources and concerns
- Avoid, minimize and or mitigate impacts with Preferred Alternative
- Coordination with permitting agencies
- Process includes public input and community development



- Bridge in serious overall condition 2009 Bridge Inspection Report
- Sufficiency Rating = 25 (out of 100)
- Superstructure in poor condition Rating = 4 out of 10
- Bridge may soon need to be load posted due to advancing deterioration of steel support members
- Deck and substructure in fair condition Rating = 5 out 10
- Bridge needs \$10M in remedial repairs.





Photo 1: South elevation

Photo 2: Bridge roadway looking east





Photo 3: Bridge opening

Photo 4: Typical spalling in top of bridge deck





Photo 5: Typical incipient spalls in underside of bridge deck - Spans 1 through 4



Photo 6: Typical spalls with exposed rebar in underside of bridge deck -Spans 1 through 4





Photo 7: Eastern flanking span (Span 7) superstructure, heavy corrosion and rusting of floorbeams, section loss of one floorbeam



Photo 8: Bascule span superstructure, corrosion and deterioration of floorbeams





Photo 9: Bascule span superstructure, corrosion and deterioration of floorbeams



Photo 10: Typical floor beam and stringers of bascule span superstructure





Photo 11: Typical corroded/rusted bascule span floorbeam



Photo 12: North girder of bascule span – heavy corrosion/rusting in bottom flange and holes in web





Photo 13: Typical heavy corrosion/rusting of girders and floorbeams, south approach spans



Photo 14: Typical heavy corrosion/rusting of floorbeams and stringers bridge approach spans





Photo 15: Typical heavy corrosion/rusting of approach span stringers

Photo 16: Typical severe corrosion of approach span bearings





Photo 17: Severe embankment erosion at west abutment



Photo 18: Pier 8 - Moderate to severe scaling and marine growth in tidal zones



Project Status

- Work began November 2011
- Data Collection Nearly Complete
 - 1. Field Survey
 - 2. Environmental Screening
 - 3. Verification of Utilities
 - 4. Obtain Bridge Inspection Reports, Traffic Data, Accident Data
 - 5. Identify Existing Substandard Design Elements
 - 6. Stakeholders and Public Involvement
 - 7. Project Fact Sheet
 - 8. Develop Project Purpose and Need



- 18 month completion schedule
- Major Milestones
 - 1. Project Purpose and Need May 2012
 - 2. Development of Conceptual Alternatives July 2012
 - 3. Select Preliminary Preferred Alternative November 2012
 - 4. Submit Draft Concept Development Report February 2013
 - 5. Completion of Concept Development Phase April 2013




Community Involvement

- Community Involvement Schedule
 - 1. Stakeholders Meeting No.1 February 15, 2012
 - Public Information Center Meeting: Purpose & Need February 27, 2012
 - 3. Stakeholders Meeting No.2: Input on Alternatives May 2012
 - 4. Local Officials Meeting September 2012
 - Public Information Center Meetings: Input on Alternatives & Selection of Preliminary Preferred Alternatives – October 2012
 - 6. Local Officials Briefing April 2013
- Comments from February 15, 2012 Stakeholders Meeting





LOCAL CONCEPT DEVELOPMENT STUDY FOR CONTRACT A MONMOUTH COUNTY BRIDGE S-32 AND MONMOUTH COUNTY ROUTE 537



Project Contact Information

- Jon Moren, Monmouth County Project Manager, (732) 308-2963
- Monmouth County Web site address:
 - visitmonmouth.com
 - Click "Departments"
 - Click "Engineering"
 - Click "Bridge & Road Projects"
- Note: This Power Point Presentation will be posted on the Monmouth County website.
- Written comments towards Project Purpose & Need will be received until Friday, March 30, 2012.



Questions & Comments

