

PROPOSAL

to the

**BOARD OF COUNTY COMMISSIONERS
COUNTY OF MONMOUTH, NEW JERSEY**

for the
Project Entitled:

**CONSTRUCTION OF A PEDESTRIAN BRIDGE
ALONG COUNTY ROUTE 12A
(NAVESINK RIVER ROAD)
AT HUBER WOODS PARK
IN THE TOWNSHIP OF MIDDLETOWN,
MONMOUTH COUNTY, NEW JERSEY**

F-104-2021

The undersigned hereby declare that he/she has carefully examined the Advertisement, Standard Specifications, Addendum(s) to Standard Specifications, Instructions to Bidders, Form of Contract and Bond for the Project named above; that he/she has carefully examined the site of the Project as provided in Section 102 of the 2019 Standard Specifications and that he/she will contract to carry out and complete said Project as specified and delineated at the prices per unit measure for each scheduled item of work stated in the Schedule of Prices.

It is understood that the total price, stated by the undersigned in the Schedule of Prices for the various item, is based on the estimated quantities and will control in the awarding of the Contract.

It is further understood that the quantities stated in this Schedule of Prices are estimates only and may be increased or decreased as provided for in the Specifications.

Submitted By:

The undersigned is a Partnership, an individual, Limited Liability Company, or a Corporation under the laws of the State of NEW JERSEY, having principal offices at

CONTRACTOR: CMS CONSTRUCTION INC.

ADDRESS: 521 NORTH AVE. PLAINFIELD, NJ 07060

TELEPHONE: 908-668-4368 FAX: 973-718-4005

BY: CARLOS DASILVA



(Printed)

(Signed)

TITLE: PRESIDENT

DATE: 07/27/2022

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**CONSTRUCTION OF A PEDESTRIAN BRIDGE ALONG COUNTY ROUTE 12A
(NAVESINK RIVER ROAD) AT HUBER WOODS PARK
IN THE TOWNSHIP OF MIDDLETOWN,
MONMOUTH COUNTY, NEW JERSEY
F-104-2021**

ITEM NO.	ESTIMATED QUANTITIES	ITEM	UNIT PRICE	AMOUNT
1.	Lump Sum	Maintenance and Protection of Traffic	\$ <u>10,000.00</u>	\$ <u>10,000.00</u>
2.	10,000 Dollar	Uniformed Police Officers Allowance	\$ <u>1.00</u>	\$ <u>10,000.00</u>
3.	2 Units	Project Identification Sign, 4'X6'	\$ <u>1,500.00</u>	\$ <u>3,000.00</u>
4.	1,000 Dollar	Fuel Price Adjustment	\$ <u>1.00</u>	\$ <u>1,000.00</u>
5.	1,000 Dollar	Asphalt Price Adjustment	\$ <u>1.00</u>	\$ <u>1,000.00</u>
6.	Lump Sum	Vibration Monitoring	\$ <u>18,000.00</u>	\$ <u>18,000.00</u>
7.	Lump Sum	Clearing Site	\$ <u>35,000.00</u>	\$ <u>35,000.00</u>
8.	4 Units	Excavation, Test Pit (If & Where Directed)	\$ <u>1,500.00</u>	\$ <u>6,000.00</u>
9.	341 C.Y.	Excavation, Unclassified	\$ <u>55.00</u>	\$ <u>18,755.00</u>
10.	87 C.Y.	I-9 Soil Aggregate	\$ <u>75.00</u>	\$ <u>6,525.00</u>
11.	238 S.Y.	Geotextile	\$ <u>2.00</u>	\$ <u>476.00</u>
12.	1,074 S.Y.	Dense-Graded Aggregate Base Course, 6" Thick	\$ <u>15.00</u>	\$ <u>16,110.00</u>
13.	655 S.Y.	HMA Milling, 3" or Less	\$ <u>15.00</u>	\$ <u>9,825.00</u>
14.	680 L.F.	Polymerized Joint Adhesive	\$ <u>10.00</u>	\$ <u>6,800.00</u>
15.	197 GAL	Tack Coat	\$ <u>12.00</u>	\$ <u>2,364.00</u>
16.	197 TON	Hot Mix Asphalt 9.5 M 64 Surface Course	\$ <u>220.00</u>	\$ <u>43,340.00</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**CONSTRUCTION OF A PEDESTRIAN BRIDGE ALONG COUNTY ROUTE 12A
(NAVESINK RIVER ROAD) AT HUBER WOODS PARK
IN THE TOWNSHIP OF MIDDLETOWN,
MONMOUTH COUNTY, NEW JERSEY
F-104-2021**

ITEM NO.	ESTIMATED QUANTITIES	ITEM	UNIT PRICE	AMOUNT
17.	234 TON	Hot Mix Asphalt 19 M 64 Base Course	\$ <u>210.00</u>	\$ <u>49,140.00</u>
18.	112 L.F.	18" Reinforced Concrete Pipe	\$ <u>190.00</u>	\$ <u>21,280.00</u>
19.	32 L.F.	21" Reinforced Concrete Pipe (If & Where Directed)	\$ <u>190.00</u>	\$ <u>6,080.00</u>
20.	1 Unit	Inlet, Type B	\$ <u>6,500.00</u>	\$ <u>6,500.00</u>
21.	1 Unit	Inlet Converted To Manhole	\$ <u>6,500.00</u>	\$ <u>6,500.00</u>
22.	1 Unit	Reconstructed Inlet, Type A, Using Existing Casting	\$ <u>2,500.00</u>	\$ <u>2,500.00</u>
23.	1 Unit	Reconstructed Inlet, Type A, Using New Casting	\$ <u>3,000.00</u>	\$ <u>3,000.00</u>
24.	106 L.F.	4'-6" High 4-Line Timber Fence	\$ <u>150.00</u>	\$ <u>15,900.00</u>
25.	8 S.Y.	Hot Mix Asphalt Driveway, 6" Thick	\$ <u>150.00</u>	\$ <u>1,200.00</u>
26.	8 S.Y.	Reset Pavers (If & Where Directed)	\$ <u>250.00</u>	\$ <u>2,000.00</u>
27.	340 L.F.	6"x8"x20" Concrete Vertical Curb	\$ <u>65.00</u>	\$ <u>22,100.00</u>
28.	425 S.Y.	Crushed Stone Layer, 6" Thick	\$ <u>25.00</u>	\$ <u>10,625.00</u>
29.	331.25 L.F.	Beam Guide Rail, Powder Coated	\$ <u>150.00</u>	\$ <u>49,687.50</u>
30.	4 Units	Tangent Guide Rail Terminal, Powder Coated	\$ <u>6,500.00</u>	\$ <u>26,000.00</u>
31.	1,600 L.F.	Traffic Stripes, Long Life, Thermoplastic 4"	\$ <u>3.00</u>	\$ <u>4,800.00</u>
32.	5 Units	RPM, Bi-Directional, Amber Lens	\$ <u>250.00</u>	\$ <u>1,250.00</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**CONSTRUCTION OF A PEDESTRIAN BRIDGE ALONG COUNTY ROUTE 12A
(NAVESINK RIVER ROAD) AT HUBER WOODS PARK
IN THE TOWNSHIP OF MIDDLETOWN,
MONMOUTH COUNTY, NEW JERSEY
F-104-2021**


ITEM NO.	ESTIMATED QUANTITIES	ITEM	UNIT PRICE	AMOUNT
33.	257 S.Y.	Topsoil Spreading, 6" Thick	\$ <u>12.00</u>	\$ <u>3,084.00</u>
34.	45 C.Y.	Borrow Topsoil	\$ <u>65.00</u>	\$ <u>2,925.00</u>
35.	257 S.Y.	Fertilizing and Seeding, Type 13	\$ <u>4.00</u>	\$ <u>1,028.00</u>
36.	257 S.Y.	Straw Mulching	\$ <u>1.00</u>	\$ <u>257.00</u>
37.	4,936 S.F.	Permanent Sheeting	\$ <u>120.00</u>	\$ <u>592,320.00</u>
38.	2,350 LB.	Reinforcement Steel, Galvanized	\$ <u>4.00</u>	\$ <u>9,400.00</u>
39.	19 C.Y.	Concrete Footing	\$ <u>1,200.00</u>	\$ <u>22,800.00</u>
40.	15 C.Y.	Concrete Abutment Wall	\$ <u>1,500.00</u>	\$ <u>22,500.00</u>
41.	Lump Sum	Temporary Shoring	\$ <u>25,000.00</u>	\$ <u>25,000.00</u>
42.	42 C.Y.	Concrete Sheet Pile Cap	\$ <u>1,650.00</u>	\$ <u>69,300.00</u>
43.	18 C.Y.	Concrete Moment Slab	\$ <u>1,200.00</u>	\$ <u>21,600.00</u>
44.	Lump Sum	Prefabricated Pedestrian Bridge	\$ <u>165,000.00</u>	\$ <u>165,000.00</u>
45.	154 C.F.	Coarse Aggregate Layer	\$ <u>15.00</u>	\$ <u>2,310.00</u>
46.	75 S.F.	Masonry Rehabilitation	\$ <u>75.00</u>	\$ <u>5,625.00</u>

TOTAL LUMP SUM BID ALL ITEMS \$ 1,359,906.50
(Numeric)

ONE MILLION THREE HUNDRED FIFTY NINE THOUSAND NINE HUNDRED SIX DOLLARS
(Written) AND FIFTY CENTS

CONTRACTOR: CMS CONSTRUCTION INC.

BY: CARLOS DASILVA
(Printed)


(Signature)

TITLE: PRESIDENT

DATE: 07/27/2022